Existing cat5e Wire&RJ45

Wall Plate (New)

RJ11 Phone Jack

1 2 3 4 5 6 7 8

RJ45 Coupler (New)

RJ45 Terminal (New)

Existing Phone Jacks in USTec Box

RJ45 Terminal (new)

RJ45 Computer Jack

1
2
3
4
5
6
7
8

Existing cat5e Cable into Wall Box

Router/Modem RJ45 Network Port (New)

USTec Custom 2-line Phone & Computer Network wiring
Utilizing existing 4-line Phone Distribution System

	BOM	QTY.
1	New Wall Plate (Dual jacked one RJ11 one RJ45)	# of Com
2	RJ45 Coupler	# of Com
3	Short lengths cat5e cable	
4	RJ45 Terminals	2x# of C
5	RJ45 Crimper	1
6	DSL/Cable Modem	1
7	Network Hub (Only if modem does not have enough ports for